

# Installation instructions

## Buoyancy control with geogrid

### To be agreed before installation:


- If the chamber manifold is installed in pressing groundwater, stratum water or slack water, this must be taken into account in the design.
- The traffic load and maximum groundwater level must be specified.  
Use the FRANK questionnaire for chamber manifolds for this (see the geothermal section at [www.frank-gmbh.de](http://www.frank-gmbh.de)).
- If groundwater level has not been considered during the static design, a sufficient drainage of seepage water must be used for soils that are impermeable to water.
- A buoyancy control system must be provided even for temporary standing water (e.g. trench during the construction period).

### Groundwater / buoyancy control

**Chamber manifolds made of FRANK spiral pipe must be secured against floatation in the case of groundwater or stratum water.**

The chamber manifold may be secured on site using a fabric mesh or a fleece fabric mesh, depending on the soil structure.

For example, you can use the Armatex G40/40 PVA woven geogrid or the Armatex MRS combi-grid 40/40-150. The grid must be secured against slipping using ground spikes.



The final mounting dimensions H 1 to 3 and b2 are defined according to the maximum groundwater level and the buoyancy calculation.

The following must be noted when laying the chamber manifold and backfilling the working area:

- The subsoil of the trench bottom must have sufficient load capacity.
- The casing is placed on a bed of sand.
- The trench must be backfilled with non-cohesive material.
- The material used for filling must be compressible, permeable, shearing resistant, frost-proof and free of sharp items (soil group G1 in accordance with ATV A 127).
- **The installation instructions for FRANK chamber manifolds must be observed.**